
Permit/Recommendation

This document is proof that a Notice of Intent has been filed as per Section 41-67-5, Mississippi Code of 1972, Annotated

December 41-07-5, Wississippi Code of 1972, Almotated		
to account the late many applies		replacement for the complete fire that such a final description
		ing the provider with the control of the property and the control of the control
grand in the second content with	Albania Romanda eta 1 Mantai eta	
Brian Hurst		Slope: 1.00 % Soil Textures:
10411 Cottage Court	John Lee Road Biloxi 3953	. ,
Diberville MS 39540	Section: 30 Townshi	p: 6S Range: 10W Sub Soil: Heavy Loam
		lantation Estates Seasonal High Water Table: 32 Inches
1	Lot Number: 21 Lot Size: 1.29 Acres	Restriction: 32 Inches
Agulfesnon:	Wanter Summers	Sensitive Waters: No
Type of Dwelling: Residence	Drinking Water: Onsite	Salshe Sie Sy hughme
Estimated Usage: 130 GPD	Dimining Water. Ottalio	ID: 160706/140205 Date Issued: 5/31/2017
Application Type:		Expiration Date: 5/31/2018
Notice Of Intent (Residential) + Final Approval (\$197.50)		Non-transferrable, valid for one (1) year from date issued.
	lons Per Day N/A = No	Notice of Intent filed: 5/25/2017
OFD-Ga	SUGAR CHARLES THE MAN THE WAY OF THE PARTY O	t Available H = Horizontal T = Triangular
Septic Tank (with baffles): 750 Gallons	Septic Tank (without baffles):	750 Gallons Advanced Treatment System (ATS): 400 GPD
	Name of the state	RPISAL
Maximum Depth: 20 Inches	Backfill Required: 4 In	AND THE STATE OF T
·		
Trench (2 ft wide) 146 Feet		97 Feet Absoration Bed 290 square feet
110000 (2 tt Wide) 140 100t	Trench (3 ft wide)	tessephon sea 250 square toet
Laura Diam (D'	Aggregate Ke	placement Options
Large Diameter Pipe	146 Feet	Chambers Total Coverage Area Required: 204 Square Feet
8 inch	146 Feet 146 Feet	Linear Footage Required for Selected Chamber Widths
10 inch	97 Feet	16": 153 Feet 22": 111 Feet 34": 72 Feet
Expanded Polystyrene System (EPS) Multi-Pipe		Multi-Pipe System (MPS)
1-12H:	200 Feet	MPS - 9 101 Feet MPS 3609 97 Feet
3-10H: 81 Feet		MPS - 11 84 Feet MPS 3611 97 Feet
2-12H: 3-10T: 73 Feet	101 Feet	MPS - 13 72 Feet MPS 3613 97 Feet
3-12H:	67 Feet	MPS - 14 97 Feet
ATS Specific Disposal Options		Additional Dignoral Ontions
Drip Irrigation 217 Feet Backfill Required N/A		Additional Disposal Options Elevated Sand Mound
	II Required N/A	Basal 289 Square Feet
Overland Discharge		Absorption 108 Square Feet
l Point N/A		
2 Point N/A		
4 Point N/A		



Notes

Author: JASON TAYLOR

Contact a licensed waste water installer. Keep wastewater system 100 feet away from all new and existing water wells.

Next Stepse

Please make several copies of this document (Permit/Recommendation), and supply to the following if applicable:

- Public utility supplying water, to receive a water meter
- * Certified well driller, if water source is from a private well
- * County Code Office (Planning Department), placement/building permit
- Certified Installer, for installation

REMINDER: Approval of the design, construction or installation of an Individual On-site Wastewater Disposal System by the Department is required. The Certified Installer is responsible for notifying the Department 24-hours before beginning installation of your Individual On-site Wastewater Disposal System and, at that time, to schedule a time for inspection of the system with the Department.

After the inspection, you must provide the Department with the following to obtain Final Approval:

- * Affidavit Installation (From the Certified Installer)
- * Affidavit Maintenance (From you, if an Advanced Treatment System was installed)
- * An additional fee of \$97.50 may be required for Final Approval, if not paid with initial application (Please see "Application" box on this form).

PLEASE BE AWARE, the Department cannot give Final Approval to any installation that occurs without inspection by the Department at the time of installation.

REMINDER: If any person or Certified Installer fails to obtain Final Approval or submit an Affidavit of proper installation to the Department in the installation of the system, the Department, after due notice and hearing, may levy an administrative fine not to exceed \$10,000,00. Also, if any person is operating in the state as an installer without certification by the Department, the Department, after due notice and opportunity for an administrative hearing, may impose a monetary penalty not to exceed \$10,000,00 for each violation as per Section 41-67-7(4) and 41-67-25(8) of the Mississippi Individual On-site Wastewater Disposal System Law.

Environmentalist Signature.

5/31/17

Mississippi State Department of Health

Revised 3-17-17

Form 335 E