STATE OF MISSISSIPPI

COUNTY OF HARRISON

AMENDMENT TO ENERGY PERFORMANCE CONTRACTING AGREEMENT BETWEEN HARRISON COUNTY, MISSISSIPPI AND MCNEIL RHOADS

THIS AMENDMENT TO ENERGY PERFORMANCE CONTRACTING AGREEMENT is entered into by and between Harrison County, Mississippi, by and through its Board of Supervisors, a political subdivision of the State of Mississippi, (hereinafter, the "County" or "Client"), and McNeil Rhoads LLC, a Mississippi Limited Liability Company, whose principal place of business is 980 N. Bierdeman Road, Pearl, Mississippi 39208, (hereinafter, "McNeil Rhoads").

WHEREAS, the County and McNeil Rhoads have previously entered into an Energy Performance

Contracting Agreement and incorporated herein by reference to implement infrastructure improvement measures throughout numerous County facilities; and

WHEREAS, improved energy performance throughout County facilities will result in substantial savings to the taxpayers of the County; and

WHEREAS, the parties desire to amend the Energy Performance Contracting Agreement to clarify certain provisions of the Agreement; and

WHEREAS, the parties hereto have the authority to enter into this Amendment to Agreement.

NOW, THEREFORE, FOR AND IN CONSIDERATION of the mutual benefits and advantages each to the other, the parties hereby acting by and through their respective authorized representatives, agree as follows:

SECTION 1. Exhibit A. Attachment 1 shall be deleted in its entirety and replaced with the enclosed Exhibit A Attachment 1.

SECTION 4. This Amendment to Agreement may be executed in more than one (1) counterpart, each of which shall constitute an original.

WITNESS OUR SIGNATURES as duly authorized for and on behalf of Harrison County, Mississippi, and

| McNeil Rhoads, LLC, on the dates indicated below. | |
|--|--|
| | HARRISON COUNTY, MISSISSIPPI |
| Date: 117-16 | Beverly Martin, Plasident Harrison County Board of Supervisors |
| (SEAL) | |
| Attest: | |
| John McAdams, Clerk of the Board | |
| John McAdanis, clerk of the Board | McNEIL RHOADS, LLC |
| | |
| Date: 11.7-16 | |
| STATE OF MISSISSIPPI COUNTY OF HARRISON | Chris McNeil, Member |
| aforesaid on this the day of November, 2016, BEV before me that they are the duly elected President of the Clerk of the Board of Harrison County, Mississippi, and foregoing instrument in writing on the date and for the | the undersigned authority in and for the jurisdiction FERLY MARTIN AND JOHN McADAMS, who acknowledged be Harrison County Board of Supervisors and duly serving that they did sign, execute and deliver the above and a purpose therein stated in the name of and for and on st duly authorized so to act by Order of the Board of NOTARY PUBLIC OF MISS. |

PERSONALLY CAME and appeared before me, the undersigned authority in and for the jurisdiction aforesaid on this the _____ day of NOVEMBER, 2016, CHRIS McNEIL, who acknowledged before me that he is the duly authorized Managing Member of McNeil Rhoads, LLC, and that he did sign, execute and deliver the above and foregoing instrument in writing on the date and for the purpose therein stated in the mane of and for and on

My Commission Expires:

STATE OF MISSISSIPPI COUNTY OF ____ behalf of McNeil Rhoads, LLC, having been first duly authorized so to act by Resolution of said limited liability company.

Tobecco Oleen

My Commission Expires:

OF MISS
OF MIS

MCNEIL RHOADS will install energy efficient lighting upgrades at the facilities listed below. A total of forty-six (46) Sites at approximately sixty (60) facilities are included in the Scope of Work.

- Summary of Fixtures Installed (approximate)
 - o 1.150 New Fixtures
 - o 9.396 Retrofitted Fixtures
 - 129 Existing Fixtures Excluded (Do Not Do)
 - o 639 Sensors

FIXTURE LENS STATEMENT

The lighting upgrade included in the scope of work is designed to maximize the energy efficiency of the lighting systems, while delivering adequate lighting levels throughout the facilities. The purpose of the upgrade is not founded in aesthetic considerations; therefore, the replacement or installation of new fixture lenses will only take place when the fixture retrofit is required to provide sufficient light levels. Older or damaged lenses that the CLIENT desires to be replaced can be addressed as extra work to this Agreement for retrofitted fixtures.

SENSORS

These sensors will be installed at MCNEIL RHOADS' discretion. The installation count may vary based on individual usage patterns and/or electrical circuitry variances.

FIXTURE COUNTS

The following tables describe the Lighting Scope of Work in depth. Fixture Counts and Quantities are approximate and may vary based actual conditions in each Facility at time of Implementation. The Final Quantities will be updated and provided in the As-built Project Documentation.

Table 1 - Lighting Retrofits Summary

| Fixtures | | |
|-----------------------------|---|------------|
| Existing | Retrofit | Count |
| 100W Incandescent | New 4' LED Wrap | 15 |
| 100W Incandescent | New 8' LED Wrap | 10 |
| 100W Incandescent | New 4' LED Wrap | 4 |
| 100W Incandescent | New 2'LED Vanity | 1 5 |
| 100W Incandescent | New LED 1x1 Canopy Light | 12 |
| 100W Incandescent Jelly Jar | New LED Mini Wallpack | 5 |
| 100W Metal Halide | Ballast Bypass and LED Corn Cob | 16 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 24 |
| 100W Metal Halide | New Small LED Flood | 9 |
| 100W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass /New Socket | 55 |
| 1500W Metal Halide Flood | HO LED Sports Lighter | 15 |
| 1500W Metal Halide Highbay | New High Output LED Highbay | 65 |
| 1500W Metal Halide Highbay | New 200w LED Highbay | 13 |
| 150W Quartz Halogen | New Small LED Flood | 12 |

| 175W Metal Halide | New LED Wallpack | 8 |
|------------------------------------|--|-------|
| 175W Metal Halide | New LED Wallpack | 107 |
| 175W Metal Halide | New LED Medium Flood | 175 |
| 18" 1T12 Existing | New LED UR Kit | 2 |
| 2' 2T12 Existing | 2x9w 2' LED Tube | 13 |
| 250W High Pressure Sodium | New LED Shoebox | 55 |
| 250W Metal Halide Gooseneck | New LED Large Flood | 53 |
| 2x2 2FT40 PL | New 2x2 Recessed Troffer w/ 2x9w 2' LED Tube | 40 |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 184 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2′ LED Tube | 67 |
| 2x2 3PL Recessed | 2x9w 2' LED Tube | 10 |
| 2x32W CFL | New LED 1x1 Canopy Light | 5 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 612 |
| 2x4 2T8 Recessed | 2x15w 4′ LED Tube | 654 |
| 2x4 3T12 Recessed | 2x15w 4' LED Tube | 492 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 894 |
| 2x4 3T8 Recessed | 3x15w 4' LED Tube | 34 |
| 2x4 3T8 Recessed | 2x4 LED Panel | 10 |
| 2x4 3T8 Recessed Parabolic Lens | 2x15w 4' LED Tube | 244 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 1,265 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 1,078 |
| 2x4 4T8 Recessed | 4x15w 4' LED Tube or UR Kits | 271 |
| 2x75W Incandescent | New LED 1x1 Canopy Light | 2 |
| 4' 1T12 Lamp and Ballast | 1x15w 4' LED Tube | 9 |
| 4' 2T12 Existing | New 4' LED Vapor Tight | 9 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 896 |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 11 |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 16 |
| 4' 2T12 Vanity | New 4' LED Vanity/Wrap | 6 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 611 |
| 4' 2T8 Non-Retrofittable | New 4' LED Wrap | 13 |
| 4' 3T12 Lamp and Ballast | 3x15w 4' LED Tube | 384 |
| 4' 4T12 Lamp and Ballast | 4x15w 4′ LED Tube | 40 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 177 |
| 4' 4T12 Non-Retrofittable | New 4' LED Wrap | 1 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 265 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 14 |
| 400W Metal Halide | 2x4 LED Panel | 42 |

| 400W Metal Halide | New 200w LED highbay | 90 |
|--|---|-----|
| 400W Metal Halide | New 200w LED highbay | 37 |
| 400W Metal Halide | New 200w LED highbay | 52 |
| 400W Metal Halide | New 8' LED Wrap | 4 |
| 400W Metal Halide | New LED Wallpack | 4 |
| 400W Metal Halide | New LED Large Flood | 26 |
| 40W G24 Globe | 8W LED Globe | 130 |
| 40W Incandescent | 7W LED A19 Lamp | 63 |
| 4x42W CFL Parking Fixture | New LED Parking Fixture | 2 |
| 60W Incandescent | 12W LED A19 Lamp | 9 |
| 65W Incandescent BR30 | 12W LED BR30 | 80 |
| 70W Metal Halide | New LED Mini Wallpack | 7 |
| 70W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 6 |
| 75W Halogen par 30 | 12W LED Par 30 | 64 |
| 75W Halogen par 30 Long Neck | 14W LED Par 30 Long Neck | 1 |
| 75W Halogen Par 38 | 17W LED Par 38 | 21 |
| 75W Incandescent | 12W LED A19 Lamp | 350 |
| 75W Incandescent | New 4' LED Vanity/Wrap | 4 |
| 8' 2T12 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 41 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 80 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 12 |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 2 |
| 8' 2T12 Non-Retrofittable | New 4' LED Wrap | 2 |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 3 |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 35 |
| 8' 2T8 | New 4' LED Vapor Tight | 2 |
| 8' 2T8 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 38 |
| 8' 2T8 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 4 |
| 8' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 9 |
| 90W Halogen Par 38 | 19W LED Par 38 | 20 |
| Candelabra E12 25W | 5W LED Candelabra E12 | 33 |
| Do Not Do Fixture | Do Not Do Fixture | 129 |
| Exit Incandescent | New LED Exit | 55 |
| N/A | Install Emergency Ballast for Security - If Needed | 77 |
| Non-Retrofittable 2T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 5 |
| Non-Retrofittable 3T12 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 7 |
| Non-Retrofittable 3T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 3x15w 4' LED Tubes | 14 |

| Non-Retrofittable 4T12 Recessed 2x4 Troffer | New 2x4 Reces | sed Troffer w/ 2x15w 4' LED Tubes | 5 |
|--|---------------|---|-------|
| Non-Retrofittable 4T8 Recessed 2x4 Troffer | New 2x4 Reces | sed Troffer w/ 2x15w 4' LED Tubes | 2 |
| Non-Retrofittable 2' 1T12 Vanity | | New 2'LED Vanity | 6 |
| T12 Circuline | Nev | w LED 1x1 Canopy Light | 101 |
| | Sens | ors | |
| Existing | | Retrofit | Count |
| N/A | | Ceiling Mount Occupancy Sensor – Wireless | 307 |
| N/A | | Hallway Occupancy Sensor – Wireless | 160 |
| N/A | | Individual Fixture Sensor | 14 |
| N/A | | New VendMiser | 28 |
| N/A | | No Sensor | 1 |
| N/A | | Passive Infrared Wall Switch, Single Switching | 8 |
| N/A | | Wall Mount Occupancy Sensor – Wireless | 4 |
| N/A | | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 72 |
| N/A | | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 42 |
| Replace Existing Pho | tocell | New Photo Cell | 3 |
| 4 2 4 2 4 2 4 2 4 2 4 2 4 4 4 4 4 4 4 4 | Sumn | nary | |
| | | | Count |
| New Fixtures | | 1,150 | |
| Retrofit Fixtures | | 9,396 | |
| Do Not Do Fixtures | | 129 | |
| Sensors | | 639 | |

| Adult Detention Facility - Mai | n Jail, Sherriff Support Services Complex | |
|---|---|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New LED 1x1 Canopy Light | 12 |
| 1500W Metal Halide Flood | HO LED Sports Lighter | 12 |
| 250W High Pressure Sodium | New LED Shoebox | 44 |
| 250W Metal Halide Gooseneck | New LED Large Flood | 38 |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 17 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 480 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 385 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 106 |
| 4' 2T12 Existing | New 4' LED Vapor Tight | 3 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 574 |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 9 |
| 4' 2T12 Vanity | New 4' LED Vanity/Wrap | 3 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 73 |
| 4' 3T12 Lamp and Ballast | 2x15w 4' LED Tube | 384 |
| 400W Metal Halide | New LED Large Flood | 26 |
| 75W Halogen Par 38 | 17W LED Par 38 | 21 |
| 75W Incandescent | 12W LED A19 Lamp | 39 |
| 8' 2T12 Non-Retrofittable | New 4' LED Wrap | 2 |
| Exit Incandescent | New LED Exit | 21 |
| Non-Retrofittable 4T12 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 1 |
| Non-Retrofittable 2' 1T12 Vanity | New 2'LED Vanity | 2 |
| T12 Circuline | New LED 1x1 Canopy Light | 100 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| New Fixtures | | 261 |
| Retrofit Fixtures | | 2,091 |
| Do Not D | 0o Fixtures | 0 |
| Sei | nsors | 0 |

| Cívic C | enter - D'Iberville | |
|---------------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 1 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 52 |
| 2x4 4T8 Recessed | 4x15w 4' LED Tube | 105 |
| 65W Incandescent BR30 | 12W LED BR30 | 80 |
| 70W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 4 |
| 75W Halogen par 30 | 12W LED Par 30 | 4 |
| 75W Incandescent | 12W LED A19 Lamp | 3 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 2 |
| N/A | Passive Infrared Wall Switch, Single Switching | 1 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 7 |
| | Summary | |
| | | Count |
| New F | ixtures | 1 |
| Retrofit | Fixtures | 248 |
| Do Not D | o Fixtures | 0 |
| Sen | sors | 10 |

| Civ | ric Center - West Harrison | |
|--------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 14 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 157 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 4 |
| 75W Halogen par 30 | 12W LED Par 30 | 20 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 2 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 4 |
| | Summary | |
| | | Count |
| | New Fixtures | 14 |
| Retrofit Fixtures | | 181 |
| Do | Not Do Fixtures | 0 |
| | Sensors | 6 |

| Civic Center - Wo | oolmarket, Senior Center - Woolmarket | | | |
|-------------------------|--|-------|--|--|
| | Fixtures | | | |
| Existing | Retrofit | Count | | |
| 175W Metal Halide | New LED Medium Flood | 8 | | |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 5 | | |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 46 | | |
| 2x4 3T8 Recessed | 3x15w 4' LED Tube | 6 | | |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 59 | | |
| 2x4 4T8 Recessed | 4x15w 4' LED Tube | 160 | | |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 3 | | |
| 75W Incandescent | 12W LED A19 Lamp | 4 | | |
| Do Not Do Fixture | Do Not Do Fixture | 16 | | |
| | Sensors | | | |
| Existing | Retrofit | Count | | |
| N/A | New VendMiser | 9 | | |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 17 | | |
| | Summary | | | |
| | | Count | | |
| | New Fixtures | | | |
| R | Retrofit Fixtures | | | |
| Do | Do Not Do Fixtures | | | |
| | Sensors | 26 | | |

| Commu | nity Center - Good Deeds | |
|------------------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 14 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 36 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 100 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 40W G24 Globe | 8W LED Globe | 48 |
| 40W Incandescent | 7W LED A19 Lamp | 1 |
| 75W Halogen par 30 | 12W LED Par 30 | 12 |
| 75W Halogen par 30 Long Neck | 14W LED Par 30 Long Neck | 1 |
| Exit Incandescent | New LED Exit | 2 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | Passive Infrared Wall Switch, Single Switching | 7 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 5 |
| | Summary | |
| | | Coun |
| New Fixtures | | 16 |
| Retrofit Fixtures | | 199 |
| Do Not Do Fixtures | | 0 |
| | Sensors | 12 |

| Commun | ity Center - Isaiah Fredericks | |
|--------------------------|--|-------------|
| Fixtures | | |
| Existing | Retrofit | Count |
| 1500W Metal Halide Flood | HO LED Sports Lighter | 3 |
| 175W Metal Halide | New LED Medium Flood | 7 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 98 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 4' 2T12 Vanity | New 4' LED Vanity/Wrap | 1 |
| 75W Incandescent | 12W LED A19 Lamp | 4 |
| 8' 2T8 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 14 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 4 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 2 |
| | Summary | |
| | | Count |
| | lew Fixtures | 8 |
| Re | etrofit Fixtures | 120 |
| Doi | Not Do Fixtures | 0 |
| | Sensors | 6 |

| Commu | inity Center - Success | |
|---|---|-------|
| Fixtures | | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 5 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 30 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 400W Metal Halide | New 8' LED Wrap | 4 |
| Do Not Do Fixture | Do Not Do Fixture | 2 |
| H40-49-49-49-49-49-49-49-49-49-49-49-49-49- | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | dendered William British British British 1995 1995 1995 1995 1995 1995 1995 199 | Count |
| New | Fixtures | 9 |
| Retrofit Fixtures | | 31 |
| Do Not Do Fixtures | | 2 |
| Se | ensors | 0 |

| | Courthouse - Biloxi | |
|---|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New 2'LED Vanity | 1 |
| 100W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 6 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 12 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 3 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 55 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 203 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 47 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 44 |
| 2x75W Incandescent | New LED 1x1 Canopy Light | 2 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 34 |
| 60W Incandescent | 12W LED A19 Lamp | 2 |
| 75W Incandescent | 12W LED A19 Lamp | 59 |
| Non-Retrofittable 2T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 1 |
| Non-Retrofittable 3T12 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 7 |
| Non-Retrofittable 3T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 3x15w 4' LED Tubes | 14 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 33 |
| N/A | Hallway Occupancy Sensor - Wireless | 14 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 4 |
| | Summary | |
| | | Count |
| New Fixtures | | 25 |
| Retrofit Fixtures | | 465 |
| Do No | ot Do Fixtures | 0 |
| | Sensors | 51 |

| Ge | ourthouse - Gulfport | |
|--|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 4 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 36 |
| 2x2 3PL Recessed | 2x9w 2' LED Tube | 10 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 513 |
| 2x4 2T8 Recessed | 2x4 LED Panel | 4 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 536 |
| 2x4 3T8 Recessed | 3x15w 4' LED Tube | 28 |
| 2x4 3T8 Recessed | 2x4 LED Panel | 10 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 285 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 74 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 67 |
| 4' 2T8 Non-Retrofittable | New 4' LED Wrap | 13 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 1 |
| 400W Metal Halide | 2x4 LED Panel | 42 |
| 60W Incandescent | 12W LED A19 Lamp | 7 |
| 75W Halogen par 30 | 12W LED Par 30 | 12 |
| 8' 2T12 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 23 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 29 |
| 8' 2T8 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 14 |
| Candelabra E12 25W | 5W LED Candelabra E12 | 8 |
| Do Not Do Fixture | Do Not Do Fixture | 4 |
| Exit Incandescent | New LED Exit | 8 |
| Non-Retrofittable 2T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 4 |
| | Sensors | 1 |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 144 |
| N/A | Hallway Occupancy Sensor - Wireless | 52 |
| | Summary | |
| | | Count |
| New Fixtures | | 21 |
| Retrofit Fixtures | | 1,707 |
| Do Not Do Fixtures | | 4 |
| | Sensors | 196 |

| Fairgrounds | - Arena, Office & Meeting Rms | |
|-----------------------------|-------------------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New 8' LED Wrap | 10 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 5 |
| 1500W Metal Halide Highbay | New High Output LED Highbay | 65 |
| 1500W Metal Halide Highbay | New 200w LED Highbay | 13 |
| 175W Metal Halide | New LED Medium Flood | 15 |
| 250W Metal Halide Gooseneck | New LED Large Flood | 10 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 4 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 1 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 8 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 14 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 2 |
| 40W Incandescent | 7W LED A19 Lamp | 1 |
| 75W Incandescent | 12W LED A19 Lamp | 3 |
| 8' 2T12 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 4 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| New Fixtures | | 119 |
| Retrofit Fixtures | | 38 |
| Do N | ot Do Fixtures | 0 |
| | Sensors | 0 |

| Court Center (E | n Offices (Bldg A), Counseling Offices (Bldg E Bldg C), Children's Shelter, Modulars | .,, |
|--------------------------|---|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 2x2 2T12 Recessed | 2x9w 2' LED Tube | 6 |
| 2x4 3T12 Recessed | 2x15w 4' LED Tube | 18 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 17 |
| 4' 1T12 Lamp and Ballast | 1x15w 4' LED Tube | 1 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 33 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 5 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 3 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 62 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 4 |
| 40W Incandescent | 7W LED A19 Lamp | 8 |
| 75W Halogen par 30 | 12W LED Par 30 | 6 |
| 75W Incandescent | 12W LED A19 Lamp | 82 |
| 75W Incandescent | New 4' LED Vanity/Wrap | 4 |
| 8' 2T12 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 2 |
| 8' 2T8 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 4 |
| Do Not Do Fixture | Do Not Do Fixture | 3 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | None | 21 |
| | Summary | |
| | | Coun |
| New Fixtures | | 4 |
| Retrofit Fixtures | | 245 |
| Do Not Do Fixtures | | 3 |
| Sensors | | 0 |

| Fire | Station - Lizana #1 | |
|--|---------------------|------|
| A STATE OF THE STA | Fixtures | |
| Existing | Retrofit | Coun |
| 100W Metal Halide | New Small LED Flood | 9 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 3 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 22 |
| 400W Metal Halide | New LED Wallpack | 4 |
| 40W G24 Globe | 8W LED Globe | 12 |
| 40W Incandescent | 7W LED A19 Lamp | 2 |
| Do Not Do Fixture | Do Not Do Fixture | 6 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | N/A | 0 |
| | Summary | |
| | | Coun |
| New | Fixtures | 13 |
| Retrofit Fixtures | | 39 |
| Do Not Do Fixtures | | 6 |
| Sensors | | 0 |

| Fire Station - West Wortham #2 | | |
|--------------------------------|-------------------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 10 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 14 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 7 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 5 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 1 |
| 400W Metal Halide | New 200w LED highbay | 6 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 2 |
| | Sensors | |
| Existing | Retrofit | Coun |
| Replace Existing Photocell | New Photo Cell | 1 |
| | Summary | |
| | | Count |
| N | lew Fixtures | 16 |
| Retrofit Fixtures | | 36 |
| Do Not Do Fixtures | | 0 |
| | Sensors | 1 |

| Fire S | tation - County Farm Rd #3 | |
|--|------------------------------------|------|
| A CONTRACTOR OF THE CONTRACTOR | Fixtures | |
| Existing | Retrofit | Coun |
| 175W Metal Halide | New LED Wallpack | 8 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 22 |
| 400W Metal Halide | New 200w LED highbay | 12 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| Exit Incandescent | New LED Exit | 2 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | N/A | 0 |
| | Summary | |
| 3 | | Coun |
| Ŋ | New Fixtures | 22 |
| Retrofit Fixtures | | 29 |
| Do Not Do Fixtures | | 0 |
| 4 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - | Sensors | 0 |

| Fire Sta | tion - County Farm #4 | |
|--|-----------------------|-------|
| List of the Control o | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 10 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 12 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 16 |
| 400W Metal Halide | New 200w LED highbay | 5 |
| 40W G24 Globe | 8W LED Globe | 11 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| New | Fixtures | 15 |
| Retrofit Fixtures | | 42 |
| Do Not Do Fixtures | | 0 |
| Se | ensors | 0 |

| Fire Station - Canal Road #5 | | |
|--|----------------------|--|
| | Fixtures | der fan skriver an en de melder witer ok en blever fan skriver fan skriver fan skriver fan skriver fan skriver |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 8 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 19 |
| 400W Metal Halide | New 200w LED highbay | 5 |
| 40W G24 Globe | 8W LED Globe | 6 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| 75W Halogen par 30 | 12W LED Par 30 | 1 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| 30 A 3 L 4 A 3 L 4 A 4 A 4 A 4 A 4 A 4 A 4 A 4 A 4 A 4 | | Count |
| New | Fixtures | 13 |
| Retrofit Fixtures | | 29 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 0 |

| Fire | Station - Delisle #6 | |
|--|----------------------|------|
| | Fixtures | |
| Existing | Retrofit | Coun |
| 175W Metal Halide | New LED Wallpack | 10 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 12 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | - 16 |
| 400W Metal Halide | New 200w LED highbay | 5 |
| 40W G24 Globe | 8W LED Globe | 11 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| | Sensors | |
| Existing | Retrofit | Coun |
| Replace Existing Photocell | New Photo Cell | 1 |
| AND THE RESIDENCE OF THE CONTRACT OF THE CONTR | Summary | |
| A Million of the Control of the Cont | | Coun |
| New | Fixtures | 15 |
| Retrofit Fixtures | | 42 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 1 |

| Fire | Station - West Harrison #7 | |
|--------------------------|---|----------|
| | Fixtures | , |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 12 |
| 18" 1T12 Existing | New LED UR Kit | 2 |
| 2' 2T12 Existing | 2x9w 2' LED Tube | 1 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 11 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 3 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 5 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 1 |
| 40W Incandescent | 7W LED A19 Lamp | 2 |
| 8' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 9 |
| Exit Incandescent | New LED Exit | 6 |
| N/A | Install Emergency Ballast for Security - If Needed | 1 |
| | Sensors | <u> </u> |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Coun |
| | New Fixtures | 18 |
| Retrofit Fixtures | | 35 |
| Do Not Do Fixtures | | 0 |
| | Sensors | 0 |

| F | ire Station - Saucier #8 | |
|--------------------------|------------------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 7 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 5 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 8 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 2 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 1 |
| 40W G24 Globe | 8W LED Globe | 9 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| Do Not Do Fixture | Do Not Do Fixture | 5 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| 1 | New Fixtures | 7 |
| . Re | etrofit Fixtures | 29 |
| Do | Not Do Fixtures | 5 |
| | Sensors | 0 |

| FI . | re Station - Success #9 | |
|--------------------------|------------------------------------|------|
| | Fixtures | |
| Existing | Retrofit | Coun |
| 175W Metal Halide | New LED Wallpack | 8 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 2 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 14 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 3 |
| 400W Metal Halide | New 200w LED highbay | 11 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| | Sensors | - |
| Existing | Retrofit | Coun |
| N/A | N/A | 0 |
| | Summary | |
| | | Coun |
| N | lew Fixtures | 19 |
| Re | etrofit Fixtures | 24 |
| Do f | Not Do Fixtures | 0 |
| | Sensors | 0 |

| Fire | Station - Bethel Road #10 | |
|--|------------------------------------|-------|
| HARMANA TANAN BERTHAMAN TANAN BERTHAMAN TANAN BERTHAMAN TANAN BERTHAMAN BERT | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 8 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 16 |
| 4' 4T8 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 3 |
| 400W Metal Halide | New 200w LED highbay | 5 |
| 40W G24 Globe | 8W LED Globe | 6 |
| 40W Incandescent | 7W LED A19 Lamp | 1 |
| 75W Incandescent | 12W LED A19 Lamp | 3 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| | New Fixtures | 13 |
| R | etrofit Fixtures | 30 |
| Do | Not Do Fixtures | 0 |
| | Sensors | 0 |

| Fire Sta | ition - North Woolmarket #11 | |
|--------------------------|------------------------------------|--|
| | Fixtures | *## ** *** *** *** *** *** *** *** *** |
| Existing | Retrofit | Coun |
| 175W Metal Halide | New LED Wallpack | 8 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 22 |
| 400W Metal Halide | New 200w LED highbay | 12 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| Exit Incandescent | New LED Exit | 2 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | N/A | 0 |
| | Summary | |
| | | Coun |
| New Fixtures | | 22 |
| Retrofit Fixtures | | 29 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 0 |

| Fire Stat | ion - East Harrison #12 | |
|---|-------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 10 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 16 |
| 400W Metal Halide | New 200w LED highbay | 11 |
| 40W G24 Globe | 8W LED Globe | 11 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| AND | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| 4 4 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | Summary | |
| | | Count |
| New | Fixtures | 21 |
| Retro | fit Fixtures | 31 |
| Do Not | Do Fixtures | 0 |
| | ensors | 0 |

| Fire | Station - Cuevas #13 | |
|--|----------------------|-------|
| 2. | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 5 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 19 |
| 400W Metal Halide | New 200w LED highbay | 5 |
| 40W G24 Globe | 8W LED Globe | 12 |
| 40W Incandescent | 7W LED A19 Lamp | 3 |
| 75W Incandescent | 12W LED A19 Lamp | 2 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| and the second s | Summary | |
| | | Count |
| Nev | v Fixtures | 10 |
| Retro | ofit Fixtures | 36 |
| Do Not | Do Fixtures | 0 |
| Sensors | | 0 |

| Fire Station | on - Henderson Point #14 | |
|--------------------|--------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 3 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 6 |
| 75W Incandescent | 12W LED A19 Lamp | 38 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Count |
| New Fixtures | | 3 |
| Retrofit Fixtures | | 44 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 0 |

| Не | aith Department - Gulfport | |
|---------------------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Metal Halide | Ballast Bypass and LED Corn Cob | 16 |
| 150W Quartz Halogen | New Small LED Flood | 4 |
| 250W High Pressure Sodium | New LED Shoebox | 11 |
| 2x2 2FT40 PL | New 2x2 Recessed Troffer w/ 2x9w 2' LED Tube | 40 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 1 |
| 2x32W CFL | New LED 1x1 Canopy Light | 5 |
| 2x4 3T8 Recessed Parabolic Lens | 2x15w 4' LED Tube | 202 |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 1 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 193 |
| 90W Halogen Par 38 | 19W LED Par 38 | 20 |
| Do Not Do Fixture | Do Not Do Fixture | 60 |
| N/A | Install Emergency Ballast for Security - If Needed | 20 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 32 |
| N/A | Hallway Occupancy Sensor - Wireless | 22 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 10 |
| | Summary | |
| | | Count |
| New Fixtures | | 61 |
| Retrofit Fixtures | | 452 |
| Do | Not Do Fixtures | 60 |
| | Sensors | 64 |

| | Human Services - Biloxi | |
|--------------------|--|-------|
| Fixtures | | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 10 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 4 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 160 |
| T12 Circuline | New LED 1x1 Canopy Light | 1 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 10 |
| N/A | Hallway Occupancy Sensor - Wireless | 10 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 3 |
| | Summary | 1 |
| | | Count |
| New Fixtures | | 11 |
| Retrofit Fixtures | | 164 |
| Do Not Do Fixtures | | 0 |
| | Sensors | 23 |

| Hun | nan Services - Gulfport | |
|---------------------------------|---|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 30 |
| 175W Metal Halide | New LED Medium Flood | 28 |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 94 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 11 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 5 |
| 2x4 3T12 Recessed | 2x15w 4' LED Tube | 468 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 16 |
| 2x4 3T8 Recessed Parabolic Lens | 2x15w 4' LED Tube | 42 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 11 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 35 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 12 |
| 75W Incandescent | 12W LED A19 Lamp | 3 |
| Exit Incandescent | New LED Exit | 4 |
| N/A | Install Emergency Ballast for Security - If Needed | 24 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 31 |
| N/A | Hallway Occupancy Sensor - Wireless | 46 |
| | Summary | |
| | | Count |
| New Fixtures | | 32 |
| Retrofit Fixtures | | 751 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 77 |

| | Justice Court - Biloxi | |
|--|---|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Metal Halide | New LED 1x1 Canopy Light | 5 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 6 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 46 |
| and the second s | Sensors | • |
| Existing | Retrofit | Count |
| | Ceiling Mount Occupancy Sensor - Wireless | 3 |
| 4444444 | Summary | |
| | | Count |
| | New Fixtures | 5 |
| Retrofit Fixtures | | 52 |
| | Do Not Do Fixtures | 0 |
| | Sensors | 3 |

Exhibit A Attachment 1 – Lighting Upgrades Scope Harrison County, MS

| J | ustice Court - Gulfport | |
|--|---|-------|
| H 6 4 30 34 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 | Fixtures | |
| Existing | Retrofit | Count |
| 100W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 10 |
| 175W Metal Halide | New LED Medium Flood | 3 |
| Do Not Do Fixture | Do Not Do Fixture | 3 |
| - Company of the Comp | Sensors | |
| Existing | Retrofit | Coun |
| N/A | N/A | 0 |
| | Summary | - |
| | | Coun |
| New Fixtures | | 3 |
| Retrofit Fixtures | | 10 |
| Do Not Do Fixtures | | 3 |
| | Sensors | 0 |

| | Fixtures | |
|--|--|----------|
| Existing | Retrofit | Coun |
| 100W Incandescent | New 2'LED Vanity | 1 |
| 100W Incandescent Jelly Jar | New LED Mini Wallpack | 1 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 6 |
| 175W Metal Halide | New LED Medium Flood | 6 |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 6 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 20 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 14 |
| 4' 2T12 Existing | New 4' LED Vapor Tight | 6 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 9 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 11 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 2 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 1 |
| 4' 4T12 Non-Retrofittable | New 4' LED Wrap | 1 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 1 |
| 400W Metal Halide | New 200w LED highbay | 39 |
| 40W Incandescent | 7W LED A19 Lamp | 1 |
| 75W Incandescent | 12W LED A19 Lamp | 22 |
| 8' 2T12 Existing | 8' 2 x 4' LED Tube w/ NEW Belly Pan | 12 |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 35 |
| Exit Incandescent | New LED Exit | 1 |
| N/A | Install Linear Fluorescent Tube Guards for Safety | 18 |
| Non-Retrofittable 4T12 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 2 |
| Replace Existing Photocell | New Photo Cell | 1 |
| | Sensors | |
| Existing | Retrofit | Cour |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 1 |
| N/A | Individual Fixture Sensor | 14 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 3 |
| | Summary | <u> </u> |
| | | Cour |
| Ne | ew Fixtures | 99 |
| Retrofit Fixtures | | 99 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 18 |

| Multi-pu | rpose Bldg - D'Iberville | |
|---|--------------------------|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 8 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 19 |
| 400W Metal Halide | New 200w LED highbay | 12 |
| Exit Incandescent | New LED Exit | 1 |
| 2-2-3-4-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1 | Sensors | |
| Existing | Retrofit | Count |
| N/A | N/A | 0 |
| | Summary | |
| | | Coun |
| New Fixtures | | 21 |
| Retrofit Fixtures | | 19 |
| Do Not Do Fixtures | | D |
| Sensors | | 0 |

| | Code/Eng & Fire | |
|---|---|----------------------|
| | ixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Medium Flood | 8 |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 6 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 35 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 97 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 3 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 1 |
| 40W Incandescent | 7W LED A19 Lamp | 10 |
| 70W Metal Halide | New LED Mini Wallpack | 6 |
| 75W Incandescent | 12W LED A19 Lamp | 2 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 1 |
| Non-Retrofittable 4T12 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 2 |
| | Sensors | who are more records |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 15 |
| N/A | Hallway Occupancy Sensor - Wireless | 6 |
| N/A | Wall Mount Occupancy Sensor - Wireless | 3 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 6 |
| S | ummary | |
| | | Coun |
| New Fixtures | | 16 |
| Retrofit Fixtures | | 155 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 30 |

| Office - Cou | nty Office Building | |
|--------------------------|--|-------------|
| | ixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New 2'LED Vanity | 6 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 3 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 2 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 18 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 68 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| Exit Incandescent | New LED Exit | 3 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 3 |
| N/A | Hallway Occupancy Sensor - Wireless | 5 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 1 |
| S | ummary | |
| | | Count |
| New Fix | New Fixtures | |
| Retrofit F | Retrofit Fixtures | |
| Do Not Do | Do Not Do Fixtures | |
| Sensors | | 9 |

| Office - El | ection Commission | |
|---------------------------------------|--|---------------|
| | Fixtures | ., |
| Existing | Retrofit | Count |
| 100W Incandescent | New 2'LED Vanity | 1 |
| 2' 2T12 Existing | 2x9w 2' LED Tube | 2 |
| 2x4 2T8 Recessed | 2x15w 4' LED Tube | 23 |
| 2x4 3T8 Recessed | 2x15w 4' LED Tube | 19 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 21 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 66 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 11 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 16 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 37 |
| 75W Incandescent | 12W LED A19 Lamp | 36 |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 2 |
| N/A | Install Emergency Ballast for Security - If Needed | 24 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 3 |
| N/A | Hallway Occupancy Sensor - Wireless | 2 |
| N/A | Wall Mount Occupancy Sensor - Wireless | 1 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 3 |
| | Summary | |
| 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | Count |
| New Fixtures | | 3 |
| Retrofit Fixtures | | 255 |
| Do Not Do | Do Not Do Fixtures | |
| Sensors | | 9 |

| Sen | ior Center - D'Iberville | |
|---|--|-------|
| Fixtures | | |
| Existing | Retrofit | Count |
| 100W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 9 |
| 175W Metal Halide | New LED Medium Flood | 12 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 50 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 69 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 12 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 22 |
| 4x42W CFL Parking Fixture | New LED Parking Fixture | 2 |
| Do Not Do Fixture | Do Not Do Fixture | 29 |
| Non-Retrofittable 4T8 Recessed 2x4 Troffer | New 2x4 Recessed Troffer w/ 2x15w 4' LED Tubes | 2 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 1 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 9 |
| | Summary | |
| | | Count |
| New Fixtures | | 16 |
| Retrofit Fixtures | | 162 |
| Do Not Do Fixtures | | 29 |
| Sensors | | 10 |

| | Senior Center - Lyman | |
|--------------------------|--|----------|
| A | Fixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New 4' LED Wrap | 14 |
| 175W Metal Halide | New LED Wallpack | 6 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 20 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 8 |
| 2x4 4T8 Recessed | 4x15w 4' LED Tube | 6 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 14 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 7 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 67 |
| 40W Incandescent | 7W LED A19 Lamp | 2 |
| 70W Metal Halide | New LED Mini Wallpack | 1 |
| 75W Incandescent | 12W LED A19 Lamp | 9 |
| Candelabra E12 25W | 5W LED Candelabra E12 | 11 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 2 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 11 |
| | Summary | |
| | | Count 21 |
| | New Fixtures | |
| | Retrofit Fixtures | |
| Do Not Do Fixtures | | 0 |
| | Sensors | |

| Senior | Center - Frances Fredericks | |
|--------------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 175W Metal Halide | New LED Wallpack | 2 |
| 175W Metal Halide | New LED Medium Flood | 2 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 59 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 49 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 10 |
| 40W Incandescent | 7W LED A19 Lamp | 1 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | New VendMiser | 8 |
| N/A | No Sensor | 1 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 9 |
| | Summary | |
| | | Coun |
| N | lew Fixtures | 4 |
| Retrofit Fixtures | | 119 |
| Do Not Do Fixtures | | 0 |
| | Sensors | 18 |

Exhibit A Attachment 1 – Lighting Upgrades Scope Harrison County, MS

| | Senior Center - Saucier | |
|---------------------|--|-------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 150W Quartz Halogen | New Small LED Flood | 8 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 75 |
| 75W Incandescent | 12W LED A19 Lamp | 1 |
| 8' 2T8 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 4 |
| Exit Incandescent | New LED Exit | 1 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Dual Circuit Switching | 8 |
| | Summary | |
| | | Count |
| New Fixtures | | 9 |
| Retrofit Fixtures | | 80 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 8 |

| Y | /ork Center (D'Iberville) | |
|--|---|-------|
| Fixtures | | |
| Existing | Retrofit | Count |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 1 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 5 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| 4' 4T12 Lamp and Ballast | 4x15w 4' LED Tube | 6 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 15 |
| 400W Metal Halide | New 200w LED highbay | 16 |
| 75W Incandescent | 12W LED A19 Lamp | 1 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 13 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 1 |
| | Summary | • |
| 4. | | Count |
| New Fixtures | | 16 |
| Retrofit Fixtures | | 45 |
| Do | Do Not Do Fixtures | |
| Sensors | | 1 |

| Work Cen | ter (Long Beach) - Garage, Office | |
|--------------------------|--|----------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Incandescent | New 4' LED Wrap | 1 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 1 |
| 175W Metal Halide | New LED Medium Flood | 8 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 2 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 26 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 2 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 4 |
| 400W Metal Halide | New 200w LED highbay | 7 |
| 75W Incandescent | 12W LED A19 Lamp | 6 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 1 |
| | Sensors | |
| Existing | Retrofit | Count |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 3 |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 2 |
| | Summary | <u> </u> |
| | | Count |
| New Fixtures | | 17 |
| Retrofit Fixtures | | 41 |
| Do | Do Not Do Fixtures | |
| Sensors | | 1 |

| | Fixtures | |
|-----------------------------|-------------------------------------|-------|
| Existing | Retrofit | Count |
| 100W Incandescent | New 2'LED Vanity | 1 |
| 100W Incandescent Jelly Jar | New LED Mini Wallpack | 2 |
| 100W Metal Halide | New LED 1x1 Canopy Light | 1 |
| 175W Metal Halide | New LED Medium Flood | 8 |
| 2' 2T12 Existing | 2x9w 2' LED Tube | 4 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 73 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 19 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 12 |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 7 |
| 75W Incandescent | 12W LED A19 Lamp | 8 |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 27 |
| Candelabra E12 25W | 5W LED Candelabra E12 | 10 |
| | Sensors | |
| Existing | Retrofit | Coun |
| N/A | · N/A | 0 |
| | Summary | |
| | | Coun |
| New Fixtures | | 12 |
| Retrofit Fixtures | | 160 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 0 |

Exhibit A Attachment 1 – Lighting Upgrades Scope Harrison County, MS

| , | Work Center (Lorraine Rd) - Wellness Clinic | | | |
|--|--|-------|--|--|
| Fixtures | | | | |
| Existing | Retrofit | Count | | |
| 100W Incandescent | New 2'LED Vanity | 2 | | |
| ' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 28 | | |
| 75W Incandescent | 12W LED A19 Lamp | 3 | | |
| ************************************** | Sensors | | | |
| Existing | Retrofit | Count | | |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 4 | | |
| | Summary | | | |
| | | Count | | |
| New Fixtures | | 2 | | |
| Retrofit Fixtures | | 31 | | |
| Do Not Do Fixtures | | 0 | | |
| Sensors | | 4 | | |

| Work Ce | nter (Lyman) - Garage, Office | | | |
|-----------------------------|---|-------|--|--|
| Fixtures | | | | |
| Existing | Retrofit | Count | | |
| 100W Incandescent | New 4' LED Wrap | 4 | | |
| 100W Incandescent | New 2'LED Vanity | 3 | | |
| 100W Incandescent Jelly Jar | New LED Mini Wallpack | 2 | | |
| 100W Metal Halide | New LED 1x1 Canopy Light | 1 | | |
| 250W Metal Halide Gooseneck | New LED Large Flood | 5 | | |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 10 | | |
| 2x4 3T12 Recessed | 2x15w 4' LED Tube | 2 | | |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 28 | | |
| 4' 2T12 Non-Retrofittable | New 4' LED Wrap | 16 | | |
| 400W Metal Halide | New 200w LED highbay | 28 | | |
| 75W Incandescent | 12W LED A19 Lamp | 5 | | |
| 8' 2T12 Non-Retrofittable | New 8' LED Wrap | 3 | | |
| | Sensors | | | |
| Existing | Retrofit | Count | | |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 5 | | |
| | Summary | • | | |
| | | Count | | |
| New Fixtures | | 62 | | |
| Retrofit Fixtures | | 45 | | |
| Do Not Do Fixtures | | 0 | | |
| Sensors | | 1 | | |

| Work Center | (Sand Beach) - Maintenance, Office | | |
|--------------------------|--|-------|--|
| Fixtures | | | |
| Existing | Retrofit | Count | |
| 2x2 2T12 Recessed U-Tube | 2x9w 2' LED Tube | 3 | |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 55 | |
| 4' 2T12 Lamp and Ballast | 2x15w 4' LED Tube | 30 | |
| 4' 2T12 Vanity | New 4' LED Vanity/Wrap | 1 | |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 4 | |
| 40W Incandescent | 7W LED A19 Lamp | 3 | |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 7 | |
| 8' 2T12 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 12 | |
| 8' 2T8 | New 4' LED Vapor Tight | 2 | |
| 8' 2T8 Existing | 8' 4 x 4' LED Tube w/ NEW Belly Pan | 6 | |
| Candelabra E12 25W | 5W LED Candelabra E12 | 4 | |
| Do Not Do Fixture | Do Not Do Fixture | 1 | |
| Exit Incandescent | New LED Exit | 1 | |
| | Sensors | | |
| Existing | Retrofit | Coun | |
| N/A | Ceiling Mount Occupancy Sensor - Wireless | 2 | |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 1 | |
| | Summary | | |
| | | Coun | |
| New Fixtures | | 4 | |
| Retrofit Fixtures | | 124 | |
| Do Not Do Fixtures | | 1 | |
| | Sensors | 3 | |

| Wo | rk Center (Woolmarket) | |
|---------------------------|--|----------------|
| | Fixtures | |
| Existing | Retrofit | Count |
| 100W Metal Halide | New LED 1x1 Canopy Light | 2 |
| 175W Metal Halide | New LED Medium Flood | 18 |
| 2' 2T12 Existing | 2x9w 2' LED Tube | 1 |
| 2x2 2T8 Recessed U-Tube | 2x9w 2' LED Tube | 5 |
| 2x4 2T12 Recessed | 2x15w 4' LED Tube | 4 |
| 2x4 3T12 Recessed | 2x15w 4' LED Tube | 4 |
| 2x4 4T12 Recessed | 2x15w 4' LED Tube | 25 |
| 2x4 4T8 Recessed | 2x15w 4' LED Tube | 3 |
| 4' 2T12 Vanity | New 4' LED Vanity/Wrap | 1 |
| 4' 2T8 Lamp and Ballast | 2x15w 4' LED Tube | 2 |
| 4' 4T12 Lamp and Ballast | 2x15w 4' LED Tube (Remove 2 Lamps) | 4 |
| 4' 4T8 Lamp and Ballast | 4x15w 4' LED Tube | 23 |
| 70W Metal Halide Rec. Can | LED 17W Par 30 Lamp w/ Ballast Bypass & New Socket | 2 |
| Exit Incandescent | New LED Exit | 3 |
| N/A | Install Emergency Ballast for Security - If Needed | 8 |
| | Sensors | · * |
| Existing | Retrofit | Count |
| N/A | Wall-Switch Occupancy Sensor, Dual Technology, Single Switching | 2 |
| | Summary | |
| | | Count |
| New Fixtures | | 24 |
| Retrofit Fixtures | | 81 |
| Do Not Do Fixtures | | 0 |
| Sensors | | 2 |